

नार्थ ईस्टर्न कोलफिल्डस्

कोल इण्डिया लिमिटेड

(एक महारत्न कंपनी)

महाप्रबंधक का कार्यालय

मार्घेरिटा - 786181 (असम)

फोन - (03751) 220283

ईपिबिरेक्स - 03751-220329 / 220339

फैक्स - 03751-220354

ई-मेल - gm.nec.cil@coalindia.in

कापोरेट आई.डी सं-L23109WB1973G01028844



NORTH EASTERN COALFIELDS

Coal India Limited

(A Maharatna Company)

Office of the General Manager

Margherita – 786181, Assam

PHONE -(03751)-220283

EPBAX- 03751 – 220329 / 220339

FAX- 03751-220354

E-mail -gm.nec.cil@coalindia.in

Corporate ID No.-L23109WB1973G01028844

पंजीकृत कार्यालय /Registered Office:महाप्रबंधक का कार्यालय/Office of the General Manager.

नार्थ ईस्टर्न कोलफिल्डस् / NORTH EASTERN COALFIELDS, कोल इण्डिया लिमिटेड/ Coal India Limited

पोस्ट/ P.O -मार्घेरिटा/ Margherita 786181,जिला/Dist.-तिनसुकिया/Tinsukia (असम)/(Assam)

पत्रांक संख्या/Ref.No: NEC/MGT/T-5/ 10 IC

दिनांक/Date: 09.04.2024

CIVIL ENGG.DEPTT : TIRAP COLLIERY

QUOTATION CORRIGENDUM

Reference to Quotation notice No: TRP/Q/C/01/2024 Dtd: 04.04.2024, there is an advertant error in the schedule of work which has been rectified and may be downloaded.

Area Manager (Civil)
NEC, CIL, Margherita.

SCHEDULE OF QUANTITY

Qtn. No. TRP/Q/C/01/2024

Dt. 04.04.2024

Name Of Work: **Erection of fencing for Quarry at Tirap Colliery.**

Sl No.	PARTICULARS	QNTY	UNIT	RATE	AMOUNT
1	Transportation of materials such as rail, Haulage rope etc. from Central store Margherita to Tirap Colliery.	1	LS		
2	Cutting of rail post and making hole for tying fencing rope including supplying of required gas and transportation of same up to near by working site.	1	LS		
3	Labour for unwinding of haulage rope complete as directed.	1	LS		
4	Carrying of rail post and metal wire rope to actual site of work manually at hilltop complete as directed.	1	LS		
5	EARTHWORK IN EXCAVATION earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified. (A) Upto a depth of 2.00 m below the existing G.L. in laminated rock or medium shale.	24.38	Cum		
6	Erection of rail post and haulage rope as directed and specified.	1	LS		
				Total Rs.	
				Add GST 18%Rs.	
				Gross TotalRs.	
(Rupes In Words)					

(N.B: Rates should be quoted in words and digits. Quotation having rates without words will be treated as invalid / incomplete and shall be rejected.

Signature of the Quotationer.