

नार्थ ईस्टर्न कोलफिल्डस्

कोल इण्डिया लिमिटेड

(एक महारत्न कंपनी)

महाप्रबंधक का कार्यालय

मार्घेरिता - 786181 (असम)

फोन - (03751) 220283

इपिबिएक्स - 03751-220329 / 220339

फैक्स - 03751-220354

ई-मेल - gm.nec.cil@coalindia.in

कापरेट आई.डी. सं-L23109WB1973G01028844



NORTH EASTERN COALFIELDS

Coal India Limited

(A Maharatna Company)

Office of the General Manager

Margherita – 786181, Assam

PHONE -(03751)-220283

EPBAX- 03751 – 220329 / 220339

FAX- 03751-220354

E-mail –gm.nec.cil@coalindia.in

Corporate ID No.-L23109WB1973G01028844

पंजीकृत कार्यालय /Registered Office:महाप्रबंधक का कार्यालय/Office of the General Manager,

नार्थ ईस्टर्न कोलफिल्डस् / NORTH EASTERN COALFIELDS, कोल इण्डिया लिमिटेड/ Coal India Limited

पोस्ट/ P.O -मार्घेरिता/ Margherita 786181,जिला/Dist.-तिनसुकिया/Tinsukia (असम)/(Assam)

पत्रांक संख्या/Ref.No: NEC/MGT/T-5/ 45 /C

दिनांक/Date: 04.05.2024

Civil Engg. Deptt.

CORRIGENDUM

With reference to the quotation notice no: NEC/MGT/QTN/43/C Dt: 03.05.2024, the figures in the quantity and unit column is missing in the uploaded bill of quantities. This has been rectified and correct form of bill of quantities is enclosed herewith and uploaded in the website. Interested bidders are requested to submit the filled up bill of quantities (which is attached herewith) along with other documents of the quotation.

Sd/-
Area Manager (Civil)
NEC, CIL, Margehrita.

SCHEDULE OF QUANTITIES FOR THE WORK - RE-CONSTRUCTION OF BOUNDARY WALL AT FRONT SIDE OF LEDO CLUB, LEDO.

(QUOTATION NOTICE NO: NEC/MGT/QTN/ 43 /C DT: 03.05.2024)

(ALL THE RATES INCLUSIVE COST OF MATERIALS AND LABOUR)

SL. NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Earthwork in excavation for foundation trenches, drain cutting and removal of surplus earth with all lead and lift as directed and specified. (in ordinary soil)	8.70	Cum		
2	Providing soling in foundation and under floor best quality picked jhama bricks, sand packed and laid to level and in panel after preparing the surface as directed (brick on flat soling)	18.88	Sqm		
3	Plain cement concrete works with coarse aggregate of sizes 13 mm to 32 mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately).in prop.1:3:6.	1.09	Cum		
4	Providing and laying plain/reinforced cement concrete works using cement,coarse sand & 20mm down graded stone aggregate with cost of necessary form work including dewatering if necessary,and curing for reinforced cement concrete work complete as directed.(Reinforcement will be measured and paid separately) including shuttering.	4.26	Cum		
5	Providing and laying plain/reinforced cement concrete works cement, coarse sand & 20 mm down graded stone aggregate including dewatering if necessary and curing complete etc. complete as directed. (M 15 grade concrete or Prop.1:2:4) in super-structure	2.17	Cum		
6	Supplying fitting and fixing in position reinforcement bars conforming to relevant I.S Code for RCC work/R.B walling including straghtening, cleaning, cutting and bending to proper shapes and length supplying and binding with 20 G black wire etc. complete as directed (Super Ductile TMT reinforcement bars)	655.16	KG		
7	Brickwork in cement mortar 1:5 with 1st class bricks including cement mortar plastering,racking out joints and curing complete as directed in superstructure above plinth level up to 1st floor level.including both side plastering in 1:4 mix.	6.37	Cum		
Total =					
GST (18% of the quoted value) =					
GRAND TOTAL =					
Rupees					

(N.B: Rates should be quoted in words and digits. Quotation having rates without words will be treated as invalid / incomplete and shall be rejected)

Signature of the contractor.