

नार्थ ईस्टर्न कोलफिल्डस्

कोल इण्डिया लिमिटेड

(एक महारत्न कंपनी)

महाप्रबंधक का कार्यालय

मार्घेरिता - 786181 (असम)

फोन - (03751) 220283

इपिबिफक्स - 03751-220329 / 220339

फैक्स - 03751-220354

ई-मेल - gm.nec.cil@coalindia.in

कापिरिट आई.डी सं-L23109WB1973G01028844



NORTH EASTERN COALFIELDS

Coal India Limited

(A Maharatna Company)

Office of the General Manager

Margherita - 786181, Assam

PHONE -(03751)-220283

EPBAX- 03751 - 220329 / 220339

FAX- 03751-220354

E-mail -gm.nec.cil@coalindia.in

Corporate ID No.-L23109WB1973G01028844

पंजीकृत कार्यालय /Registered Office:महाप्रबंधक का कार्यालय/Office of the General Manager,

नार्थ ईस्टर्न कोलफिल्डस् / NORTH EASTERN COALFIELDS, कोल इण्डिया लिमिटेड/ Coal India Limited

पोस्ट/ P.O -मार्घेरिता/ Margherita 786181,जिला/Dist.-तिनसुकिया/Tinsukia (असम)/(Assam)

पत्रांक संख्या/Ref.No: NEC/MGT/T-5/266/1/C

दिनांक/Date: 21.10.2024

Civil Engg. Deptt.

### CORRIGENDUM

With reference to the quotation notice no: NEC/MGT/QTN/264/C Dt: 18.10.2024, there is a typing error in the quantity column of SL.No: 6 of the uploaded bill of quantities. This has been rectified and correct form of bill of quantities is enclosed herewith and uploaded in the website. Interested bidders are requested to submit the filled up rectified bill of quantities (which is attached herewith) along with other documents of the quotation.

Sd/-  
Area Manager (Civil)  
NEC, CIL, Margehrita.

**SCHEDULE OF QUANTITIES FOR THE WORK - LIGHTING ARRANGEMENT AT POLOFIELD, MARGHERITA.**

REF. QUOTATION NOTICE NO: NEC/MGT/QTN/ 264 /C DT: 18.10.2024

(ALL THE RATES INCLUSIVE COST OF MATERIALS AND LABOUR)

SL. NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Earthwork in excavation for foundation trenches of walls, retaining walls, footing of columns, steps, septic tank etc. including refilling the quantity as necessary after completion of work, braking clods in return filling, dressing, watering, ramming etc. and removal of surplus earth with all lead and lift as directed and specified.(in ordinary soil)..	3.46	Cum		
2	Providing soling in foundation and under floor with stone/best quality picked jhama brick, sand packed and laid to level and in panel after preparing the surged as directed including all labour and materials and if necessary dewatering, complete.	2.88	Sqm		
3	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps,wall,brick works etc.as directed and specified including dewatering if necessary, and curing complete.	3.74	Cum		
4	Providing form work of ordinary timber planking so as to give a rough finish including entering, shuttering, strutting and propping etc. height of propping and entering below supporting floor to ceiling not exceeding 4.0m and removal of the same for in situ reinforced concrete and plain concrete work in Sides and soffits of beams,beam haunching etc.	24.96	Sqm		
5	Welding of old rail post into straight post with necessary push brace pole with necessary arrangement of clamping of lights as directed	8.00	Nos		
6	Supplying and erection of L.T stay set complete (galvanized) with 19 mm dia x 1.8 mm long stay rod anchor plate of size 30 cm x 30 cm x 6.4 mm thimble stay clamps turn buckle (19 mm x 60 cm) 7/14 SWG dia G.I stay and strain insulation etc. in cement 1:3:6 (1 cement: 3 course sand: 6 graded stone aggregate) 40 mm nominal size foundation including excavation and refilling etc. as required and as directed by the department.	8.00	LS		
<b>Total =</b>					
GST (18% of the quoted value) =					
<b>GRAND TOTAL =</b>					
Rupees (In words)....					

(NB: Rates should be quoted in words and digits. Quotation having rates without words will be treated as invalid / incomplete and shall be rejected.)

**Signature of the Contractor**