नार्थ ईस्टर्न कोलफिल्डस् कोल इण्डिया लिमिटेड

(एक महारत्न कंपनी) महाप्रबंधक का कार्यालय मार्घेरिटा - 786181 (असम)

फोन - (03751) 220283

ईपिबिएक्स - 03751-220329 / 220339

फैक्स - 03751-220354

ई-मेल gm.nec.cil@coalindia.in

कापरिट आई.डी सं-L23109WB1973G01028844



NORTH EASTERN COALFIELDS

Coal India Limited

(A Maharatna Company) Office of the General Manager Margherita - 786181, Assam PHONE .-(03751)-220283 EPBAX-03751 - 220329 / 220339 FAX- 03751-220354

E-mail _gm.nec.cil@coalindia.in

Corporate ID No.-L23109WB1973G01028844

पंजीकृत कार्यालय /Registered Office:महाप्रबन्धक का कार्यालय/Office of the General Manager, नार्थ ईस्टर्न कोलफिल्डस् / NORTH EASTERN COALFIELDS, कोल इण्डिया लिमिटेड/ Coal India Limited पोस्ट/ P.O -मार्घेरिटा/ Margherita 786181,जिला/Dist.-तिनसुकिया/Tinsukia (असम)/(Assam)

पत्रांक संख्या/Ref.No: TKK/C/169/2025

दिनांक/Date: 25.08.2025

CIVIL ENGG. DEPTT: TIKAK COLLIERY

QUOTATION CORRIGENDUM

Reference to Quotation notice No: TKK/Q/C/160/2025 Dtd: 20.08.2025 and Quotation notice no: TKK/Q/C/161/2025 Dt: 20.08.2025, there is an advertant error in the schedule of work (BOQ) which has been rectified and may be downloaded against the above mentioned notice nos.

> Area Manager (Civil) NEC, CIL, Margehrita.

| uota | tion Notice No.: TKK/Q/C/ 161 /2025 | | | | Dated: 20.08.2025 |
|------|--|---------|------|---------------|-------------------|
| | Of Work: Erection of towards a line of the state of the s | | | | |
| NO | Erection of temporary kitchen and toilets for A | AAAOUNT | | | |
| - | Description | QNTY | UNIT | RATE | AMOUNT |
| 1 | White washing with lime on wall surfaces (two coats) to give an even shade including throughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter. | 1012.50 | Sqn | | |
| 2 | a) Colour washing with lime on wall surface (two coats) over and including a priming coat of white washing to give an even shade after throughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter. | 871.40 | Sqm | | |
| 3 | c) Applying one coat of dry distemper of approved brand and manufacture on old wall surface after throughly brushing the surfaces free from mortar droppings and other foreign matter and including preparing the surface even and sand papered smooth including Extra subsequent one coat. | 248.00 | Sqm | | |
| | | | | Total R | 5. |
| | | | | Add GST 18 | % |
| | | | | Gross Total R | s. |
| | Ruppes | | | | |

SIGNATURE OF TENDERER

| Quotation Notice No.: TKK/Q/C/ 160 /2025 Dated: 20.08.2025 | | | | | | | | | |
|--|--|--------|------|-----------------|---------------------------------------|--|--|--|--|
| Name | Of Work: Erection of townsorans kitchen and tallets for | | | | Dated: 20.08.2025 | | | | |
| | Erection of temporary kitchen and toilets for AISF at Tikak Colliery. | | | | | | | | |
| SL No | Description | QNTY | UNIT | RATE | AMOUNT | | | | |
| 1 | EARTHWORK IN EXCAVATION earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and revomal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified. (A) Upto a depth of 2.00 m below the existing G.L.in hard / dense soil. | 5.83 | Cum | | | | | | |
| 2 | Making of bamboo roof and wall structure for temporary structure shed complete as directed. | 1.00 | LS | | | | | | |
| 3 | Providing corrugated galvenised Iron sheet roofing of TATA SHAKTEE/SAIL including fitting and fixing necessary galvanised Jor L hooks , bolts and nuts 8 mm dia with bitumen washer 25 mm dia x 3 mm thick and 1.6 mm thick limpet washer complete excluding coast of roof truss, purlin etc. (Roof trussedd and purlin etc. to be measured and paid separately) | 193.64 | Sqm | | | | | | |
| 4 | Transportation of building materials for the enclouser at Margherita and Tirap Colliery as requierd. | 7.00 | LS | | | | | | |
| 5 | 25 mm thick cement concrete tooping 1:2:4 (1 cement: 2coarse sand : 4 coarse aggregate of 12 mm nominal size) finished with a floating coat of neat cement finish (base concrete to be measured and paid separately) to be laid in panels including curing complete as directed. | 16.66 | Sqm | | | | | | |
| 6 | Providing sleeping masang with necessary bhaluka bamboo post etc. complete as directed. | 43.20 | Sqm | | | | | | |
| 7 | Earth/sand filling in plinth in layers not more than 150 mm thick including necessary carriage, watering, ramming etc. complete as directed and specified including payment of land compensation, forest royalty, sales tax and other duties and taxes as may be necessary. | 13.57 | Cum | | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | | | | |
| 8 | Providing brick soling in foundation and under floor with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete: | 18.52 | Sqm | | | | | | |
| 9 | Providing, fitting and fixing vitreous water closet squatting pan(indian type w.c orissa pattern) with all fitting and fixing complete.size 580 x 450 mm | 2.00 | NO | | | | | | |
| | | | | Total Rs. | | | | | |
| And the second s | | | | Add GST 18% | | | | | |
| | | | | Gross Total Rs. | | | | | |
| | Ruppes | | , | | | | | | |
| 33 | | | | | | | | | |